FARM ACCESS ROAD SPECIFICATION

1. Remove topsoil from road width plus 500mm on either side. Stockpile for re-use.
2. Excavate in sub-soil to formation level. Stockpile for re-use.
3. Excavate and remove to tip any unsuitable material found below formation level. Upfill with suitable material and compact in 200 layers.
4. Grade and compact formation to falls.
5. Lay and compact selected coarse graded granular material (Class 6F2/6F3) in 250 thick layer.
6. Lay and compact to finished shape Type 1 crushed rock sub-base in 150 thick layer. Blind any open areas with crusher dust.
7. Backfill verges with topsoil and grass seed.
8. Erect 5 strand post and wire fence 1 metre back from edge of new roadline and tie into existing fences.
9. Excavate and remove to tip section of existing access track no longer required.
10. Upfill with stockpiled topsoil to provide same depth as alongside the access track.
11. Remove surplus sub-soil and topsoil to tip.

KEY

- THC Site
- Access
- Visibility Splays
- Service Wayleaves
- Works for Third Parties

| SCHEDULE OF OFFSITE WORKS | Action |
|---|---|
| 1. Access Road to adoptive standards and associated drainage and buried services.<br>2. Implement 40mph speed limit on B9090.<br>3. Pumping main and connection to Scottish water sewers.<br>4. Pedestrian Crossing.<br>5. Traffic lights at junction.<br>6. Visibility splays at junction.<br>6a. Visibility splays at existing junction (requirement being contested).<br>7. New access road for farm.<br>8. Relocate any existing services on track.<br>9. Remove defunct access track.<br>10. Footpath link into village with associated lighting.<br>11. Scottish Water connection from public highway along access road.<br>12. S&SE connection from pole mounted transformer.<br>13. Split ducting of existing S&SE HV cable at B9090 junction.<br>14. BT ductwork to be laid from public highway along access roadway. | |

SCHEDULE 16
REF. SECTION 2.

Revised 7 March 2007

Scottish Water Main

Scottish Water Man Hole

| SERVICE | DESCRIPTION |
|---|---|
| NATURAL GAS | N/A |
| WATER | SCOTTISH WATER (INVERNESS) REF MS/DA/H/1A 19,24,25&28 DATE 11/03/04 |
| LPG (HEATING) | NO OFF SITE WORKS |
| OIL | N/A |
| BT | |
| ELECTRICITY (KITCHEN) | |

| Reference | Existing | Proposed |
|---|---|---|
| 11,000 volt overhead lines | | |
| Low voltage overhead lines | | |
| 11,000 volt underground cables | | |
| Low Voltage underground cables | | |
| Service cables | | |
| Transformer Positions | | |
| Duct Positions | | |

B. Access road changed to green shading. Add Farm Access Road Spec. Extend wayleave NW. 14.11.05 JF.

A. Wallace Whittle & Nortec utilities information added. Schedule for offsite works added. Access and third party works areas amended/added. Various notes added. 19.09.05 DAC.

| Revisions | Date | By |
|---|---|---|


**A.F.Cruden Associates**
Consulting Engineers
24 Bank Street
Inverness IV1 1QU
Tel: 01463 716200
Fax: 01463 716201
email: cruden@cal.com


Client
ALPHA SCHOOLS/
THC EDUCATION
DEPARTMENT

HIGHLAND SCHOOLS PFP2

Project
CAWDOR PRIMARY SCHOOL

Drawing
OFF-SITE WORKS

Issue WARRANT

Drawing No. CA3278/CAWP/PW/19
Drawn By DAC
Date 15.09.05
Rev.B
Scale 1:1000 at A1

This drawing is copyright of A.F.Cruden Associates