

Corran Ferry
The Ferry Office
Ardgour
Fort William
PH33 7AA



Tel: 01855 841243

CorranFerry.Office@highland.gov.uk

<https://www.highland.gov.uk/corran-ferry>

Annual Out of Water Survey & Refit – Emergent Work

The Highland Council	Corran Ferry	Vessel Name	Maid of Glencoul
Refit	Spring 2026	PC Renewal	08 March 2026

Vessel Particulars

Official Number	361323	Year of Build	1975
IMO Number	7521613	Radio Call Sign	MEHH7
UK Class	V	Rating	Cat C
PAX	116	PCU	14
Length (m)	32.00	Gross Tonnage	166.73
Breadth (m)	10.10	Deadweight (T)	77
Draft (m)	1.20	Power	Diesel
Propulsors	Screw	Drivetrain	Mechanical
Electrics	AC 110V / DC 24V	Engine Power	410.3KW

Annual Out of Water Survey & Refit – Emergent Work			
The Highland Council		Corran Ferry	Vessel Name Maid of Glencoul
1	Major Repair Works		
1.1	Hull Steel Patching Hull thickness survey identified hull steel patching required FWD and AFT. 40 m ² total. Emergency fire pump impacted – renew valve. Temporarily move ships ballast to allow access.		
1.2	Wheelhouse Hot Steel Patching & repairs above deck level includes: • Wheelhouse base • X4 legs and patches/attachment (superstructure/deck) • Scaffolding • Replace cable glands • Repair & enlarge cable junction box cupboard		
1.3	Wheelhouse Rewiring: • Due to hot steel works, proximity of the cables, perished cable glands and the age and condition of the cables, the wheelhouse repairs require removal and then reinstallation of cables from the wheelhouse to the vessel (approximately half of the cables). • Those cables previously replaced (to steering and engine room) do not require replacing due to new condition and location.		
2	MCA Survey Deficiencies		
	 Hydraulic valve block – install oil drip trays x2 Overhaul emergency fire pump main valves (x2) Engine room bilge suction – replace strum box Fuel Tank – replace sight gauge with new – tbc by MCA		

Annual Out of Water Survey & Refit – Emergent Work			
The Highland Council		Corran Ferry	Vessel Name Maid of Glencoul
3	Other Repairs		
	Discovered during prep for painting - FWD nav light mounting plate to be replaced. - Starboard wheelhouse door frame to be replaced. Required during hot steel works - Remove Anchor and Anchor Chain from anchor chain locker to gain access for hull steel welding work. Chip and paint Anchor and Anchor Chain as required. - Anchor Cradle to be repaired. - Additional storage bar to be added into FWD shaft space for rope stowing.		

Annual Out of Water Survey & Refit – Emergent Work			
The Highland Council	Corran Ferry	Vessel Name	Maid of Glencoul
Document Control			

Document No	MOG-EW-2026-1				
Prepared By	██████	Role	Engineering Superintendent	Date	28/04/2026
Reviewed By	████████	Role	Operations Manager	Date	28/04/2026
Approved By	██████	Role	Chief Officer	Date	29/04/2026

Revision No	MOG-EW-2026-2				
Details	3. Other Repairs				
Prepared By	██████	Role	Engineering Superintendent	Date	08/05/2026
Reviewed By	████████	Role	Operations Manager	Date	08/05/2026
Approved By	██████	Role	Chief Officer	Date	14/05/2026

Revision No					
Prepared By		Role		Date	
Reviewed By		Role		Date	
Approved By		Role		Date	